

COMMERCIAL PLASTERBOARD ESTIMATING SYSTEM



TIMBERLINE®
SOLUTION PROVIDER



INDUSTRY DATABASE & TIMBERLINE SOFTWARE

INTRODUCING the next era in estimating! Our system is computerised – reduce time spent hand estimating with this very fast and super accurate system.

PEWin - C:\PEV10\PLCOM

File Edit View Database Takeoff Pricing Reports Interface Window Help

Commercial

| Group | Cost Code | Description | Takeoff Quantity | Labour Price | Labour Amount | Material Price | Material Amount | Total Cost/Unit | Total Amount |
|---------------|---------------|----------------------------------|------------------|--------------|---------------|----------------|-----------------|-----------------|--------------|
| 04.000 | | PLASTERING | | | | | | | |
| | 04.050 | 10mm R/E Plasterboard | | | | | | | |
| | | Cartage 10mm | 195.30 m2 | - | - | 51.38 /to | 66 | 0.34 /m2 | 66 |
| | 04.750 | Plasterboard Accessories | | | | | | | |
| | | 10mm Masonry Drills | 1.48 ea | - | - | 20.00 /e | 30 | 20.00 /ea | 30 |
| | | 25mm Nylon Anchors x 6.5 | 148.10 m | - | - | 10.00 /f1 | 24 | 0.16 /m | 24 |
| 09.000 | | LABOUR | | | | | | | |
| | 09.550 | Fix Ceilings | | | | | | | |
| | | Fix Grid-(exp lay-in 1200*600) | 195.30 M2 | 34.50 /hr | 796 | - | - | 4.08 /M2 | 796 |
| | | Fix Tiles (lay-in 1200*600) | 195.30 M2 | 34.50 /hr | 490 | - | - | 2.51 /M2 | 490 |
| | 09.600 | Fix Trim Columns/Trims | | | | | | | |
| | | Cut and Trim Columns Square | 2.00 each | 34.50 /hr | 69 | - | - | 34.50 /each | 69 |
| | | Cut Holes for Downlights Tile | 2.00 each | 34.50 /hr | 12 | - | - | 5.75 /each | 12 |
| | | Cut Holes for Recess Lights Tile | 1.00 each | 34.50 /hr | 3 | 1.15 /e | 1 | 4.03 /each | 4 |
| | | Labour for AC Registers - Tile | 1.00 each | 34.50 /hr | 3 | 1.00 /e | 1 | 3.88 /each | 4 |
| | | Labour for Sprinklers | 4.00 each | 34.50 /hr | 12 | - | - | 2.88 /each | 12 |
| | | Labour for Speakers | 4.00 each | 34.50 /hr | 23 | - | - | 5.75 /each | 23 |
| | 09.750 | Labour Rates | | | | | | | |
| | | Wall Trim Labour | 59.24 lm | 3.00 /m | 178 | - | - | 3.00 /m | 178 |
| 10.000 | | CEILING TILES | | | | | | | |
| | 10.100 | Ceiling Tiles & Grid | | | | | | | |
| | | Armstrong Fissured | 195.30 m2 | - | - | 9.35 /e | 2,536 | 12.99 /m2 | 2,536 |
| | 10.120 | Minerial fibre Chng Tis | | | | | | | |
| | | 1200 x 600 Tile | 194.94 m2 | - | - | 6.00 /e | 1,624 | 8.33 /m2 | 1,624 |
| 12.000 | | SUSPENDED CEILING SYST | | | | | | | |
| | 12.100 | Primary Sections | | | | | | | |
| | | 24x32mm C.R.-T.WV 1200 Ron CRS2 | 332.01 m | - | - | 1.28 /t | 510 | 1.54 /m | 510 |
| | | 24x32mm C.R.-T.WV 400 Ron CRS2 | 332.01 m | - | - | 0.84 /L | 697 | 2.10 /m | 697 |
| | | 24x38mm M.R. Proc 300C-TVV R440 | 46.83 m | - | - | 4.24 /L | 55 | 1.18 /m | 55 |
| | 12.800 | Wall Angle / Bulhead Trim | | | | | | | |
| | | R/F lipped W/A 19x19 ron284 | 59.24 m | - | - | 3.01 /t | 50 | 0.84 /m | 50 |
| | 13.200 | Suspension Rod Brackets | | | | | | | |
| | | susp-rod bracket conc ron247 | 97.65 ea | - | - | 0.18 /e | 18 | 0.18 /ea | 18 |

Cost Code/Item Takeoff Order Assembly Material Class Location BOQ ITEM STAGE

For Help, press F1

23/04/01

ABOVE IS A TYPICAL EXPOSED GRID SUSPENDED CEILING TAKE-OFF SHOWING ALL OF THE COMPONENTS INCLUDING LABOUR AND ACCESSORIES

COMMERCIAL PLASTERBOARD ESTIMATING SYSTEM

FEATURES

Sorts Projects by Location, Types etc.


Take-off & Prices at the same time

Calculates Labour & all Accessories

Complete Bill of Materials & Order List

Uses Digitiser for pin point accuracy

SAVE UP TO 2/3's OF YOUR ESTIMATING TIME



DIGITISER

A computerised drawing board that you put a plan On and trace the lengths and automatically sends the Measurements to the computer.

TYPICAL COMMERCIAL APPLICATIONS

All Board types covered

51, 64, 76, 92mm Steel Stud Ceilings

Suspended Ceilings & Plasterboard Ceilings

Facade & Soffit Systems

Glass & Aluminium Systems