

Win more Business with

DOMESTIC PLASTERBOARD ESTIMATING SYSTEM



INDUSTRY DATABASE & TIMBERLINE SOFTWARE

INTRODUCING the next era in estimating! Our system is computerised – reduce time spent hand estimating with this very fast and super accurate system.

Group	Cost Code	Description	Takeoff Quantity	Labour Price	Labour Amount	Material Price	Material Amount	Total Cost/Unit	Total Amount
04.000		PLASTERING							
	04.002	Packlot Plasterboard							
		10mm r/e plasterboard 6.0x1.2m	314.93 m2	-	-	26.57 /sht	1,162	3.69 /m2	1,162
		10mm r/e plasterboard 6.0x1.2m	-10.00 m2	-	-	26.57 /sht	-37	3.69 /m2	-37
		10mm r/e plasterboard 6.0x1.2m	-26.86 m2	-	-	26.57 /sht	-99	3.69 /m2	-99
		10mm r/e plasterboard 6.0x1.2m	3.60 m2	-	-	26.57 /sht	13	3.69 /m2	13
		10mm WR Board 3.6x1.2m	3.60 m2	-	-	22.46 /sht	19	5.20 /m2	19
	04.007	Ceilings							
		10mm ceiling pboard 6.0x1.2m	178.36 m2	-	-	26.57 /sht	658	3.69 /m2	658
	04.009	Cornices							
		90mm Std Cornice 4.8m	134.22 m	-	-	6.53 /lth	183	1.36 /m	183
	04.011	Externals / Internals							
		Metal External Angle 2400	5.00 no	-	-	1.53 /ea	8	1.53 /no	8
		Metal Ext Obtuse Angle 2400	2.00 no	-	-	1.08 /ea	2	1.08 /no	2
		Metal Internal Angle 2400	6.00 no	-	-	2.07 /ea	12	2.07 /no	12
		Metal Obtuse Int Angle 2400	5.00 no	-	-	2.65 /ea	13	2.65 /no	13
		Archway Edging Bead 3000	2.00 no	-	-	1.54 /ea	3	1.54 /no	3
	04.013	Domestic Labour							
		Setting Labour	463.61 m2	2.00 /m2	927	-	-	2.00 /m2	927
		Archways - large	2.00 ea	180.00 /ea	360	-	-	180.00 /ea	360
		Splays	7.00 ea	6.00 /ea	42	-	-	6.00 /ea	42
		Freight	463.61 m2	-	-	0.30 /m2	139	0.30 /m2	139
		10mm Wall Fix Labour	281.65 m2	2.50 /m2	704	-	-	2.50 /m2	704
		Ceilings Fix Labour	178.36 m2	2.50 /m2	446	-	-	2.50 /m2	446
		Externals Fix Labour	11.00 no	6.00 /ea	66	-	-	6.00 /no	66
		Cornice Fix Labour	134.22 m	2.00 /m	268	-	-	2.00 /m	268
		WR Board Fix Labour	3.60 m2	2.50 /m2	9	-	-	2.50 /m2	9
	04.030	Plboard Domestic Access							
		Paper Tape 75m Roll	463.61 m2	-	-	3.05 /ROLL	14	0.03 /m2	14
		25mm Plasterboard Screws	1,408.24 ea	-	-	10.12 /bag	14	0.01 /ea	14
		25mm Plasterboard Screws	891.80 ea	-	-	10.12 /bag	9	0.01 /ea	9
		GB100 Base Coat 20kg	463.61 m2	-	-	18.60 /bag	48	0.10 /m2	48
		Joint Master 25kg	463.61 m2	-	-	22.90 /bail	53	0.11 /m2	53
		Cornice Cement 45 20Kg	134.22 lm	-	-	21.90 /bag	29	0.22 /m	29

ABOVE IS A TYPICAL PLASTERBOARD HOUSE TAKE-OFF WITH ALL COMPONENTS NEEDED FOR THE JOB INCLUDING LABOUR AND ACCESSORIES AND DEDUCTIONS FOR WINDOWS AND DOORS

DOMESTIC PLASTERBOARD ESTIMATING SYSTEM

FEATURES

Optimises board, allows for Wall Openings


Optimises ceiling by Room

Does Packlot and Room by Room Take-off

Complete Bill of Materials & Order List

Uses Digitiser for pin point accuracy

SAVE UP TO 2/3's OF YOUR ESTIMATING TIME



DIGITISER

A computerised drawing board that you put a plan On and trace the lengths and automatically sends the Measurements to the computer.

TYPICAL DOMESTIC APPLICATIONS

Wet & Dry Areas

Half & Full Rake Ceilings

Wardrobes, Internals, Externals

Standard & Decorative Cornices

All Accessories & Labour calculated automatically